BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Name of Work: Immersion of Ganesha Idols in Sahakaranagara Kalyani in ward no 10, Kempapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	195.00	Earth work excavation by manual means for drains,canals, waste weir draft, approach channels, key trench, foundation of Bridges and such similar works, as per drawing and technical specifications, including setting out, shoring, strutting, barricading, caution lights, excavated surface leveled and sides neatly dressed disposing off or leveling the excavated stuff or sorting & stacking the selected stuff for reuse in a radius of 50 m and lift upto 1.5 m including cost of labour, tools, usage & other appurtenances required to complete the work. In ordinary / soft rock without blasting upto 1.5 m depth	Cum	251.90	Rupees Two Hundred Fifty One and Ninety Paise Only
2	61.00	Depth exceeding 1.5m, but not exceeding 3.00 m	Cum	375.10	Rupees Three Hundred Seventy Five and Ten Paise
3	2.50	Stone crusher dust finer than 3mm 100 metal Component	Cum	1460.00	Rupees One Thousand Four Hundred Sixty
4	180.00	Supply of water Through water Tank for filling Tank	L	360.00	Rupees Three Hundred Sixty Only
5	18.00	Hire charge of pumping water 3.5 KL/hr capacity Pump	Hr	42.00	Rupees Forty Two Only
6	55.00	Providing Causal Labours (Unskilled mazdoor Heavy)	Nos	486.22	Rupees Four Hundred Eighty Six and Twenty Two
7	660.00	Hire Charges of Barricade Triple line per meter	Mtr	80.00	Rupees Eighty Only
8	3300.00	Hire Charges of Cloth and Pipe Shamiyana	Sft	14.00	Rupees Fourteen Only
9	44.00	Hire Charges of Side Wall Size 10 x 8 per Wall	Nos	350.00	Rupees Three Hundred Fifty Only
10	110.00	Hire Charge for Plastic Chairs	Nos	5.50	Rupees Five and Fifty Paise Only
11	33.00	Hire Charge for Table cloth ordinary per table	Nos	120.00	Rupees One Hundred Twenty Only
12	330.00	Hire Charge for supplying and running circuit service main with necessary messanger wire and reel insulators and maintaining the same 4 of 25 samm PVC insulated and sheathed aluminium	Mtr	9.00	Rupees Nine Only
13	55.00	Generator 100 KVA	Hr	1303.00	Rupees One Thousand Three Hundred Three
14	55.00	Hire charges for Focus lighting arrange ments for the stage and existing immersion Tank during night time	Nos	650.00	Rupees Six Hundred Fifty Only

Name of Work: Immersion of Ganesha Idols in Sahakaranagara Kalyani in ward no 10, Kempapura

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
15	33.00	Mobile Hydraulic Crane 3t capacity	Hr	788.00	Rupees Seven Hundred Eighty Eight Only

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

Note:

1 Item for which no rate or price has been entered in will not be paid for by the Employer when executed and shall be deemed covered by the other rates and prices in the Bill of quantities (refer: ITB Clause 7.2 and CC Clause 33.2)

2 Unit rates and prices shall be quoted by the Tender in Indian rupees.

3 Where there is a discrepancy between the rate in figures and words the rates in words will govern (ITB Clause 19.1(a)

4 Where there is a discrepancy between the unit rate and the line item total resulting from multyplying the unit rate by quantity the unit rate quoted shall govern (ITB Clause 19.1(b))